





**Retrieval of Damaged Components  
from Experimental Fast Reactor Joyo  
Reactor Vessel**

**June . 8<sup>th</sup> , 2010**

**Yukimoto MAEDA**

**Japan Atomic Energy Agency (JAEA)**

# Experimental fast reactor JOYO




Main cooling building

Containment vessel


# Role of JOYO

To confirm the performance of sodium cooled FBR power plant

Prototype fast breeder reactor power plant MONJU  
280MWe (714MWt)



Commercial power plant




Experimental fast reactor JOYO  
140MWt



- To confirm the principle of sodium cooled FBR
- To establish operation, maintenance technology
- Irradiation for fuels and materials development using fast neutron field

# Outline of JOYO



Dump heat exchanger

Secondary pump

Containment vessel

Control room

IHX

Primary pump

Reactor vessel

**Major specs**

Type : Loop type (2 loops)

Rated power : 140 MWt

Fuel : MOX

Core Structure : Stainless steel

Coolant : Liquid sodium

Core diameter : 80 cm

Core height : 50 cm

Start of construction : 1970

Operation (breeding core : MK - I) : 1978


(irradiation core : MK-II) : 1982

Upgrading core ( MK-III) criticality : July 2003

Start of irradiation with MK-III core : May 2004




# JOYO heat transport system



Cooling system type : Loop type  
Number of main cooling system : 2  
Heat Removal : Air Cooling




# History of Joyo



# Upgrading of the Joyo cores

**MK-I core**


**Breeder core**



**50/75MWt**

**MK-II core**


**Irradiation core**



**100MWt**


**MK-III core**

**Upgraded  
Irradiation core**



**140MWt**

- |                          |                             |
|--------------------------|-----------------------------|
| Control rod              | Subassembly for irradiation |
| Core fuel subassembly    | Shielding subassembly       |
| Reflector                | Inner core fuel subassembly |
| Blanket fuel subassembly | Outer core fuel subassembly |





# Installation of New Main IHX




Transport from Warehouse to Maintenance Building



Move from Maintenance Building to RCV



Move inside RCV



Stand-up



Lift-down



Installation Completed


# Background

- On June 11th 2007, fuel handling machine was set up on the rotating plug (R/P) as a refueling preparation.
- The measured load of hold down shaft indicated abnormal decrease in the R/Ps jack down operation.




It was suspected that there was an obstacle under the hold down shaft.

- The in-vessel storage rack under the hold down shaft stored an irradiation rig “MARICO-2”.
- As a result of visual inspection, an obstacle around in-vessel storage rack was identified as the MARICO-2 test subassembly.



# Structure of MARICO-2






MARICO : MAterial testing Rlg with temperature COntrol




**Drive mechanism**

**Guide tube**

**Test subassembly**




# In-Vessel Inspection of Sodium cooled Fast Reactor




# In-vessel visual observation by camera

## - Bent MARICO-2 on in-vessel storage rack -




- Grasp the conditions of the transfer pot and the bent MARICO-2.



# In-vessel visual observation by camera


## - Top of the subassemblies and in-vessel storage rack-

- No damage to each handling head of subassembly and in-vessel storage rack







Composite photograph

3 mm in width



Handling Head


# In-vessel visual inspection by fiberscope



- Radiation resistant fiberscope was applied to observation.
- Fiberscope was inserted in the reactor vessel through the in-vessel inspection holes.





# Results of observation by fiberscope

- Clear image was obtained by radiation resistant fiberscope.
- Grasp the condition of the bent MARICO-2.






# Visual inspection device for UCS bottom





# Results of UCS bottom face observation



UCS bottom face

Sodium flow regulating grid


MARICO-2 upper guide tube



MARICO-2 upper guide tube

Handling head


Handling head connected with holding mechanism



Thermocouple




Deformed regulating grid

# 3-D image of bent MARICO-2 test assembly



# Replace UCS and retrieve MARICO-2 test S/A

1. Remove the existing UCS
2. Retrieve the MARICO-2 through the hole from which UCS is removed
3. Insert new UCS



# Major subjects of UCS replacement

## (1) High radioactivity of UCS

- **UCS cask weight (preliminary evaluation) : >110 ton**
- **Allowable load of C/V crane : 100 ton**

**Reducing UCS cask weight**

## (2) Sodium deposition between UCS and small-R/P

- **Overload during UCS removal**
- **Deformation of UCS and small-R/P**

**Proper evaluation of sodium deposition**

## (3) UCS inclination control


- **Minimum gap between UCS and small-R/P : 5 mm**

**UCS jack-up device with severe inclination control**

## (4) Prevent impurity ingress to the sodium system

- ⇒ **Control of cover gas pressure, impurity concentration monitoring etc.**

( Experience of cooling system renovation in MK-III modification work )




# Measure for reducing UCS cask weight

## Cask design target

- UCS cask weight : <100 ton (including UCS 16.5 ton)
- Surface dose rate of cask : <1 mSv/h

### (1) In-vessel gamma dose measurement

- Optimization of cask thickness based on dose rate distribution of UCS measured value




#### Detector

Type : Ionization chamber (IC)  
Range : 0.1~1000 Gy/h



### (2) Optimization of UCS cask structure

- Variations of thickness : 2 → 4
- \* From a manufacturing standpoint, two kind of thickness is better.



# Dose rate on UCS surface

## - Evaluation Method -

**Neutron flux calculation**

**2-D transport code DORT**

↓ **Neutron flux,  $\sigma$**


**Gamma-ray source calculation**

**ORIGEN2**

↓ **Gamma-ray source**

**Gamma-ray flux calculation**

**QAD-CGGP2**




↓ **Conversion to dose : ICRP74**

**Calculated gamma dose rate**




↓ **Corrected by measured value**

**Dose rate distribution on UCS**



# Dose rate on UCS surface


## - Evaluation results -



**Sodium flow regulating grid**

450mm

# Shielding design result of UCS cask



Position		Thickness (cm) (Carbon steel)	Dose rate on cask surface ( $\mu\text{Sv/h}$ )
Top ⑥		10	<50*
Side	⑤	10	132
	④	14	525
	③	21	627
	②	27	564
Bottom ①		29	896


\* : The top of the cask (⑥) satisfies allowable dose rate (1mSv/h) with 0mm in thickness. Taking account of cask strength, ⑥ has same thickness as ⑤.



**Total weight of UCS cask : ~93.4ton**  
**( with UCS (16.5 ton))**  
**below allowable load of crane (100ton)**

# Retrieval procedure of bent MARICO-2

## Access route



## Geometric condition

UCS can not be positioned right above the bent MARICO-2 to avoid a contact with it.




The retrieval device employs  
***“offset configuration”***


# Lifting-up test device of bent MARICO-2 (1)

**Lifting-up test was planned to confirm:**


- bent MARICO-2 can be lifted-up
- stuck of bent MARICO-2 with pot or not



Lifting-up test device




# Lifting-up test device of bent MARICO-2 (2)



*Lifting-up simulation test was conducted to confirm :*

- Holding function of bent part of wrapper tube
- Adjustment against position difference etc.
- Visual condition by optical fiber



# Lifting-up test




**Lifting-up device**  
( In-vessel  
inspection hole (A) )

**Insertion of device**

**Fiberscope**  
(Fuel handling hole)

Large R/P

UCS



**Adjusting angle of fingers**


Small R/P

**MARICO-2**

# Lifting-up test of bent MARICO-2


Nov. 18<sup>th</sup> 11 : 00

Insertion of fingers




12 : 47

Finger position adjustment




14 : 15

Bent MARICO-2 lifting-up




**The picture was obtained by fiberscope during lifting-up operation.**

# Measured load during lifting-up test




- (a) Increasing load for lifting-up drive shaft (0mm)
- (b) Lifting-up drive shaft only (0-5.5mm)
- (c) Increasing load for lifting-up MARICO-2 with pot (5.5-10.5mm)
- (d) Lifting-up MARICO-2 with pot (10.5-43mm)
- (e) Lifting down



**This result indicated that bent MARICO-2 was lifted-up together with pot, but the rack was not stuck with pot.**




# Master Schedule for Joyo Resumption





# Joyo's Roles for FBR Fuel Cycle Development



\* ODS: Oxide Dispersion Strengthened Ferritic Steel

# Summary

- In-vessel visual inspections were successfully conducted by fiberscope and video camera. These results are reflected to the restoration work of Joyo.
- The design of retrieval device of damaged UCS and bent MARICO-2 has been almost finished based on the radioactivity evaluation of UCS and lifting test of bent MARICO-2.
- Valuable experience and data are obtained through restoration work.